Travis J. Underhill, PE Deputy Commissioner Mark Bailey, PE Office of Hydraulics Manager

CEPDS November 15, 2018



• Disciplines where INDOT has removed itself from the LPA design world

• Pavement Design Design Memo <u>18-01</u>, effective February 5, 2018

Design Memo <u>18-08</u>, effective May 9, 2018

• Hydraulics Design Memo 18-12, effective July 1, 2018

• Traffic Design T.B.D.

Geotechnical

• Environmental T.B.D.

• Road Design T.B.D.

Bridge Design T.B.D.



- Sources of Information
 - Design Memos https://www.in.gov/dot/div/contracts/standards/memos/memos.html
 - LPA Programs https://www.in.gov/indot/2390.htm
 - Subscribe to the LPA Important Notices email list https://www.in.gov/indot/files/LPA InstructionsToSubscribe.pdf
 - Project Development Process Guidance Document <u>https://secure.in.gov/indot/files/LPA GuidanceDocument 042015.pdf</u>
 - Design Certification for Non-National Highway System Projects https://www.in.gov/indot/files/LPA Certification Program.pdf
 - Indiana Design Manual https://www.in.gov/indot/design manual/



孠

LPA Programs





Railway-Highway Crossings Section 130 Program



Local Federal Aid Program

U.S. Department of Transportation Federal Highway Administration




INDOT LPA Design Certification Program



- Local Public Agency (LPA)
- All local government units
 - Counties
 - Cities
 - Towns



• If your project was on the INDOT RFP List, it's not an LPA project. https://pscs.indot.in.gov/rfppublicwebsite/





• LPA projects are advertised here. https://www.in.gov/dot/div/legal/rfp/LPARFP/LPARFPcurrentlyadvertised.htm

INDOT » DOING BUSINESS WITH INDOT » REQUEST FOR PROPOSALS » LPA - REQUEST FOR PROPOSALS

LPA - RFP Current Advertisements

- <u>La Porte County Government Lincoln Trail Extension along Abandoned RR just west of 421 to PNW (Des # 1801831) in La Porte District</u>

 **Response Due Date & Time: December 13, 2018 at 4:00 pm
- Floyd County Preliminary Engineering for Bridge #51 Replacement (Des # 1700788) in Seymour District (Revised 11/07/18)
 Response Due Date & Time: November 30, 2018 at 4:00 pm
- Hamilton County Highway This project will establish an improved E-W corridor linking 276th St with 281St St. then making improvements to connect to 5 19. (Des # 1600597) in Greenfield District

Response Due Date & Time: November 16, 2018 at 4:00 pm

Hamilton County Highway, Rehabilitation of 236th St. from Deming Rd to Tollgate Rd, west of Cicero, IN (Des # 1400788) in Greenfield District
Response Due Date & Time: November 16, 2018 at 4:00 pm



• Design Memo <u>18-12</u>, effective July 1, 2018

The Department has updated the Office of Hydraulics responsibilities for LPA projects on locally owned, non-NHS routes. The following guidance now applies.


LPA Project on a Locally Owned, Non-NHS Route

- Pipes/Small Culverts (span < 4ft). The Office of Hydraulics will not review these structures.
- Locally owned? Is your project on an Interstate, State Road, U.S. Route or within State owned R/W (prisons, parks, etc.)?
- NHS routes? https://secure.in.gov/indot/2350.htm
 - National Highway System





• NHS routes https://secure.in.gov/indot/2350.htm



• Interactive NHS Map Viewer (Zoom and pan to selected NHS highway segments)

• Estimated MAP-21 NHS Mileage

















- Pipes / Small Structures and Bridges
 - LPA project
 - Locally owned
 - Non-NHS route
 - Existing span is < 4′, no review
 - Existing span is 4' or larger
 - Proposed structure is one mile or less downstream of an INDOT structure (measured along the stream)
 - Proposed backwater does not dissipate before reaching an upstream INDOT structure.
 - Proposed structure is ½ mile or less upstream of an INDOT structure (measured along the stream)
 - There are levees within the proposed project limits.



• Proposed structure is one mile or less downstream of an INDOT structure (measured

along the stream)





• Proposed structure is one mile or less downstream of an INDOT structure (measured along the stream)









• Proposed backwater does not dissipate before reaching an upstream INDOT

structure.






 Proposed structure is ½ mile or less upstream of an INDOT structure (measured along the stream)



- There are levees within the proposed project limits.
- https://levees.sec.usace.army.mil/#/








• Side Cast Berms <u>do not</u> count as levees.







- Storm Drains
 - Requirements for Review by the Office of Hydraulics
 - Where any drainage from the LPA project is received by INDOT Right of Way (ROW)
 - Where any drainage from INDOT ROW is received by the LPA system
 - Detention when drainage is received by INDOT ROW







- What to do if your projects meets all of the conditions of Design Memorandum No. 18-12?
 - Another condition!
 - Any Select Bridge project, as defined by the Historic Bridge Programmatic Agreement (dated July 17, 2006), to be delivered and constructed as a federal-aid project will not be qualified to participate in this program.
 - You may have options with the design criteria you use.
 - If the LPA is a certified LPA they have the option of utilizing local standards and criteria.
 - As of last week the list of Certified LPA's included:
 - Boone County
 - Brown County
 - City of Carmel
 - City of Fishers
 - City of Franklin
 - City of Westfield
 - Porter County
 - You still prepare and submit a report and models as part of the projects design calculations.
 - INDOT will review a sample of projects completed by certified LPAs. The current plan is a random selection of 10% of projects.

- Answers to common questions:
 - If LPA is not Certified, all designs per IDM.
 - If your project no longer qualifies for an INDOT review but was previously reviewed and returned with comments for a resubmittal, the resubmittal will not be reviewed.
 - If your project does not qualify for an INDOT review but you want one, LPA needs to request the review. Comments will be provided, but INDOT will not issue formal approval, acceptance or denial. Only general observations and comments will be provided.





